TheItalianTasker
Phone: 07737422842
Email: theitaliantasker@gmail.com

Free ANKARUDDEN Assembly Checklist

A simple one-page checklist covering parts, alignment, doors, drawers, wall anchoring and final safety checks. (Placement: Immediately after the Final Inspection section.)

Ready to build your ANKARUDDEN wardrobe? Keep your assembly, drawers, doors, and safety checks organized from start to finish.

DOWNLOAD THE FREE ASSEMBLY CHECKLIST

1. PARTS INVENTORY & WORKSPACE SETUP

- [ ] **Panels & Carcass Components Audited:** Verify all top, base, side panels, backboards, sliding door slabs, and drawer components before unboxing [cite: 18].
- [ ] **Hardware & Fasteners Grouped:** Sort cam-locks, dowels, connecting bolts, drawer runners, and door track rollers into sorting trays [cite: 11, 18].
- [ ] **Workspace Floor Protection Laid:** Flatten cardboard packaging across the assembly perimeter to shield panels and flooring from scratches [cite: 7, 11, 26].

2. FRAME ASSEMBLY & CARCASS ALIGNMENT

- [ ] **Carcass Fixings Fully Torqued:** Ensure every structural bolt, cam-lock, and dowel across base, sides, and top panels is securely tightened [cite: 74].
- [ ] **Diagonal Squareness Confirmed:** Measure corner-to-corner diagonally before securing back panels to eliminate chassis twist and binding tracks [cite: 14, 16, 74].
- [ ] **Base Leveled for Uneven Floors:** Check baseline with a spirit level and adjust leveling feet or shims so the unit rests safely backward against the wall [cite: 18, 24, 74].

3. SLIDING DOORS & DRAWER FUNCTIONALITY

- [ ] **Drawer Runners Installed & Tested:** Confirm drawer glides operate smoothly, stop buffers catch properly, and drawer fronts sit flush with even reveals [cite: 74].
- [ ] **Sliding Doors Track-Aligned:** Verify upper and lower guide channels are debris-free, rollers glide smoothly across the track, and door leaves overlap evenly [cite: 74].

4. WALL ANCHORING & FINAL SAFETY CHECKS

- [ ] **Partition Scanned & Anchored:** Sweep wall with an electronic multi-detector for cables/pipes, then fasten anti-tip brackets into solid timber studs or masonry [cite: 2, 8, 10, 14, 74].
- [ ] **Zero Unexplained Components Remaining:** Audit the workspace to confirm no brackets, connecting bolts, or shelf pegs remain unaccounted for [cite: 74].

🚨 **Mandatory Anti-Tip Safety Notice:**
Tall wardrobes must never be loaded until wall anchoring is 100% complete [cite: 74]. For professional flat-pack assembly across London with guaranteed fixed pricing, contact our expert installation team [cite: 20, 24].