TheItalianTasker
**Phone:** 07737422842
**Email:** theitaliantasker@gmail.com

# Free HAUGA Wardrobe Assembly Checklist

*A printable preparation, assembly and final-safety checklist to help you organise the build from start to finish. (Ideal placement: Immediately after the Final Inspection section.)*

## 1. PREPARATION & WORKSPACE SETUP

- [ ] **Room & Ceiling Clearances Measured:** Verify available width, depth, and vertical ceiling height, accounting for skirting boards and door opening space [cite: 5].
- [ ] **Workspace Floor Protection Laid:** Flatten cardboard packaging across the assembly zone to protect both furniture laminate and room floor finishes [cite: 7, 11, 26].
- [ ] **Hardware Inventory Sorted:** Organize all wooden dowels, cam-locks, connecting screws, and hinges into trays to confirm no missing factory parts [cite: 11, 18].

## 2. CARCASS ASSEMBLY & ALIGNMENT

- [ ] **Frame Diagonals Checked for Squareness:** Measure corner-to-corner diagonally before securing back panels to prevent permanent chassis twist and binding tracks [cite: 14, 16].
- [ ] **Base Leveled for Uneven Floors:** Check floor baseline with a spirit level and adjust leveling feet or shims so the wardrobe frame leans safely backward against the wall [cite: 18, 24, 26].
- [ ] **Sliding Door Tracks & Rollers Installed:** Ensure top and bottom guide tracks are clear of debris and rollers seat correctly for smooth, silent gliding.

## 3. FINAL INSPECTION & SAFETY SIGN-OFF

- [ ] **Wall Substrate Scanned & Anchored:** Sweep wall with an electronic multi-detector for cables/pipes, then secure anti-tip brackets into studs or masonry [cite: 2, 8, 10, 14, 28].
- [ ] **Door Alignment & Smooth Gliding Tested:** Test sliding doors across the entire span to ensure zero sticking, level margins, and proper buffer stop engagement.
- [ ] **Zero Unexplained Spare Components:** Audit the workspace to confirm all structural brackets, shelf pegs, and fasteners are installed with no leftover parts.

🚨 **Mandatory Anti-Tip Safety Sign-Off:**
Never load shelves or drawers until wall anchoring is 100% complete [cite: 10, 13, 14]. For professional assistance across London with guaranteed fixed pricing, contact our expert installation team [cite: 20, 24].