TheItalianTasker
Phone: 07737422842
Email: theitaliantasker@gmail.com

Free KLEPPSTAD Wardrobe Assembly Checklist

A printable checklist covering preparation, parts, assembly, alignment and final safety checks. (Placement: Immediately after the Final Inspection Checklist section.)

Preparing to assemble your KLEPPSTAD wardrobe? Download the free checklist and keep your preparation and safety checks organised from start to finish.

1. PREPARATION & WORKSPACE SETUP

- [ ] **Room & Ceiling Clearances Measured:** Confirm layout width, depth, and vertical ceiling height, accounting for skirting boards and door clearance [cite: 5].
- [ ] **Workspace Floor Protection Laid:** Flatten cardboard packaging across the footprint to shield furniture laminate and floor finishes from scratches [cite: 7, 11, 26].

2. PARTS & HARDWARE INVENTORY

- [ ] **Panels & Carcass Components Counted:** Inspect all panels (top, base, sides, backboard, and doors) for transit damage before starting assembly [cite: 18].
- [ ] **Fixings & Fasteners Grouped:** Sort dowels, cams, screws, and runners into sorting trays to ensure no missing hardware delays the build [cite: 11, 18].

3. CARCASS ASSEMBLY & SQUARING

- [ ] **Carcass Built & Fasteners Fully Seated:** Ensure every structural dowel and connector is firmly tightened across top, base, and side panels to eliminate frame flex [cite: 66].
- [ ] **Frame Diagonals Checked for Squareness:** Measure diagonally corner-to-corner before attaching back panel to avoid permanent frame twist [cite: 14, 16, 66].

4. LEVELING & DOOR ALIGNMENT

- [ ] **Base Leveled for Uneven Floors:** Use a spirit level to check floor level and insert shims as needed so the unit leans safely back against the wall [cite: 18, 24, 66].
- [ ] **Sliding Doors Installed & Glide Tested:** Verify door tracks are clean, runners glide smoothly without sticking, and panel overlap margins align evenly [cite: 66].

5. FINAL SAFETY & SIGN-OFF

- [ ] **Wall Anchoring Completed:** Scan wall for wires/pipes and secure anti-tip brackets into solid timber studs or masonry using correct wall fixings [cite: 2, 8, 10, 14, 66].
- [ ] **Zero Unexplained Components Remaining:** Verify no structural brackets, shelf supports, or fixings were left out or forgotten in the box [cite: 66].

🚨 **Mandatory Anti-Tip Safety Notice:**
Tall wardrobes must always be anchored securely to the wall before loading clothes or shelves [cite: 66]. For professional flat-pack assembly across London with guaranteed fixed pricing, contact our expert installation team [cite: 20, 24].