TheItalianTasker

Phone: 07737422842
Email: theitaliantasker@gmail.com

Interactive Checklist — Is Your ANKARUDDEN Ready?

> *An interactive post-assembly verification checklist to confirm structural stability, smooth drawer and door operation, and complete wall anchoring before loading your wardrobe.*

FINAL INSPECTION & SAFETY SIGN-OFF

- [ ] **All required fixings installed**
  Confirm all structural cam-locks, dowels, connecting bolts, and internal bracket screws are fully tightened across the entire frame to prevent joint play.

- [ ] **Frame correctly aligned**
  Verify that the carcass is plumb, level, and square diagonally from corner to corner so internal shelves seat evenly and side panels stay true.

- [ ] **Drawers operate correctly**
  Check that all drawer runners glide smoothly on their tracks, stop buffers engage cleanly, and drawer front panels align with consistent gaps.

- [ ] **Sliding doors move smoothly**
  Ensure guide channels and rollers are free of debris, door leaves travel effortlessly across the entire track span, and end-stops catch securely.

- [ ] **Wall anchoring completed**
  Confirm mandatory anti-tip safety brackets are firmly fastened into solid wall studs or masonry using fixings specifically matched to your wall substrate.

- [ ] **No unexplained components remain**
  Cross-reference the assembly hardware guide to ensure no forgotten brackets, structural screws, or shelf pins were left behind in the workspace.

🚨 **Mandatory Anti-Tip Safety Notice:**
Tall wardrobes must never be loaded until wall anchoring is 100% complete. Do not store heavy clothing or fill drawers until safety brackets are fully secured to prevent tipping hazards.