TheItalianTasker
Phone: 07737422842
Email: theitaliantasker@gmail.com

Interactive Checklist — Is Your PAX / GRIMO Ready?

> *An interactive post-assembly sign-off checklist to verify structural stability, hinge alignment, KOMPLEMENT internal movement, and safety wall anchoring before loading your wardrobe.*

FINAL INSPECTION & SAFETY VERIFICATION

- [ ] **All required fixings are installed**
  Confirm every cam-lock, connecting bolt, and structural dowel across top, bottom, and side panels is fully torqued and flush to eliminate joint play.
- [ ] **Frame is correctly aligned**
  Verify that the PAX carcass is plumb, level, and cross-diagonally square so that GRIMO doors hang straight with uniform, consistent reveals.
- [ ] **Doors and storage features work smoothly**
  Check that GRIMO hinged doors open without binding, soft-close dampers engage quietly, and KOMPLEMENT drawers, baskets, and pull-out trays glide freely.
- [ ] **Wardrobe is stable**
  Ensure the frame rests firmly on the floor without wobble or rocking, with front leveling feet adjusted to compensate for uneven floor contours.
- [ ] **Wall anchoring is complete**
  Confirm anti-tip brackets are securely fixed into wall studs or solid masonry using heavy-duty fixings matched to your wall substrate.
- [ ] **No unexplained components remain**
  Cross-check the assembly inventory to confirm that no structural brackets, hinge mounting plates, or shelf supports remain unaccounted for.

🚨 **Mandatory Anti-Tip Safety Sign-Off:**
Tall PAX wardrobes must never be loaded until wall anchoring is 100% complete and tested. If any frame lean or binding is detected, adjust base feet and bracket tension immediately before use.